

Office of The Superintending Engineer, N.H. Planning & Design Circle,
P.W (Roads) Directorate
Govt. of West Bengal

1ST CORRIGENDA & ADDENDA to NH Schedule of Rates for ROAD & BRIDGE Works 2015-16

A.

Serial No.	Chapter No.	Page No.	Item No.	Column No.	To be read as	In Place of
					Item	Item
1	8	146	4	2	2 Providing & fixing of retro reflectorised cautionary, mandatory and informatory sign as per IRC: 67 made of high intensity grade sheeting vide clause 801.3 fixed over aluminium sheeting 1.5mm thick, when signs with maximum side dimensions do not exceed 600mm, or with aluminium sheeting 2.0mm thick when signs with maximum side dimensions exceeds 600mm, supported on a mild steel angle iron post 75mmx75mmx6mm firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 45cmx45cmx60cm, 60cm below ground level as per approved drawing (Reference to MoRT&H's specification 801)	2 Providing & fixing of retro reflectorised cautionary, mandatory and informatory sign as per IRC: 67 made of high intensity grade sheeting vide clause 801.3 fixed over aluminium sheeting 1.5mm thick supported on amild steel angle iron post 75mmx75mmx6mm firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 45cmx45cmx60cm, 60cm below ground level as per approved drawing (Reference to MoRT&H's specification 801)
2	17	291	3	2	Supplying & fixing of Aluminium Flexible Prismatic Sheeting (AFP) consisting of non metallic prismatic lenses that are formed in a transparent , synthetic resin; sealed and backed with a conformable aluminium foil backing with an aggressive pressure sensitive adhesive and with an easily removable liner. This flexible prismatic reflective sheeting used in the product specified herein should be of yellow colour and have minimum values of retro reflection coefficient, which shall conform to Type VI of ASTM D4956-09.. After application of the flexible prismatic sheeting to required application areas, all the edges of the flexible prismatic sheeting should be sealed with two part epoxy based structural adhesives with epoxy having viscosity of 8000-14000 mPa.s when measured as per ISO 12058, which should show extreme resistance to peel off. The contractor will have to provide a test certificate from a reputable national/international laboratory conforming the above specifications.	Supplying & fixing of Aluminium Backed Flexible Prismatic of 3M make (The above is inclusive of Adhesive)
3	17	292	6	2	Supplying & fixing of Raised Pavement Markers/Road Studs/Cats Eye made of polycarbonate moulded body and reflective panels with micro prismatic lens capable of providing total internal reflection of the light entering the lens face which shall support a load of 13635 kg tested in accordance to ASTM D 4280 Type H and complying to Specifications of Category A of MoR&TH Circular No. RW/NH/33023/10-97 - DO III Dt. 11.06.1997 & MoRT&H's specification for Road & Bridge Works (Fifth Rev.). Marker height shall not be less than 10 mm and shall not exceed 20 mm, width shall not exceed 130mm and with minimum reflective area of 13 sqcm on each side and slope to the base shall be 35 ± 5 degree. Fixing will be without nails but by using epoxy resin based adhesive as per manufacturer's recommendation including site clearance etc and complete as directed by the Engineer in Charge. The contractor will have to provide a test certificate from a reputable national/international laboratory conforming the above specifications.	Supplying & fixing of Raised Pavement Marker (CATS EYE) conform to ASTN D 4280, body of the marker will be moulded from polycarbonate. The Marker double sided lens YELLOW / WHITE /RED colour. Dimension : 20mm height,130mm width and 105 mm length , 3 M make.
4	A	30	8.22 (i)	-	RCC M40 grade concrete = 0.30 cum per m as per sl. No. 14.1	RCC M 25 grade concrete = 0.30 cum per m as per sl. no. 14.1

All other things remain unchanged.

B.

Corrigendum to Sl. No. 22 of Chapter 8 (Traffic Signs, Markings and Other Road Appurtenances), Page No. 154 is given below:-

TO BE READ AS				
Serial No.	Item	Unit	Rate (Rs.)	Remarks
			Labour, T&P, Machinery etc.	
1	2	3	4	5
	Reinforced Cement Concrete Crash Barrier : Provision of an Reinforced cementconcrete crash barrier at the edges ofthe road, approaches to bridge structures and medians, constructed with M-40 grade concrete with HYSD reinforcement conforming to IRC:21and dowel bars 25 mm dia, 450 mm long at expansion joints filled with premoulded asphalt filler board, keyed to the structure on which it is built and installed as per design given in the enclosure to MOST circular No. RW/NH - 33022/1/94-DO III dated 24 June 1994 as per dimensions in the approved drawing and at locations directed by the Engineer, all as specified (Reference to MORT&H's specification 811).	RM	259.60	Cost of all material included. Only the cost of material for RCC M-40 & HYSD steel reinforcement to be added as per chapter A Sl.No. 8.22
IN PLACE OF				
Serial No.	Item	Unit	Rate (Rs.)	Remarks
			Labour, T&P, Machinery etc.	
1	2	3	4	5
	Reinforced Cement Concrete Crash Barrier : Provision of an Reinforced cement concrete crash barrier at the edges of the road, approaches to bridge structures and medians, constructed with M-30 grade concrete with HYSD reinforcement conforming to IRC:21 and dowel bars 25 mm dia, 450 mm long at expansion joints filled with premoulded asphalt filler board, keyed to the structure on which it is built and installed as per design given in the enclosure to MOST circular No. RW/NH - 33022/1/94-DO III dated 24 June 1994 as per dimensions in the approved drawing and at locations directed by the Engineer,all as specified (Reference to MORT&H's specification 811).	RM	223.50	Cost of all material included. Only the cost of material for RCC M-30 & HYSD steel reinforcement to be added as per chapter A, Sl.No. 8.22

C.

The items given below is an addenda to the NH Schedule of Rates 2015-2016 which is to be treated as Serial no 8,9,10 & 11 of Chapter 17 of the Schedule of Rates and as a continuation of the existing Schedule of Rates

Serial No.	Item	Unit	Rate (Rs.)	Remarks
			Labour, T&P, Machinery etc.	
1	2	3	4	5
8	Bituminous Macadam Providing and laying bituminous macadam using crushed aggregates of specified grading premixed with bituminous binder, transported to site, laid over a previously prepared surface with paver finisher to the required grade, level and alignment and rolled as per clauses 501.6 and 501.7 to achieve the desired compaction (Reference to MORT&H's specification clause 504).			
8a	With Continuous Type HMP (60-90 TPH)			
(i)	for Grading 1 (40 mm nominal size)	cum	1046.50	This is as per MoRT&H No. RW-24011/02/2014-Mech Dated 11.12.2015 Cost of materials to be added . Consumption of materials to be followed as per Ch. A., Sl.No. 5.3 This item is to be used after getting prior approval of the concerned S.E.
(ii)	for Grading 2 (19 mm nominal size)	cum	1046.50	
8b	With Continuous Type HMP (40-60 TPH)			
(i)	for Grading 1 (40 mm nominal size)	cum	1042.20	
(ii)	for Grading 2 (19 mm nominal size)	cum	1042.20	
	1.Quantity of Bitumen has been taken for analysis purpose. The actual quantity will depend upon job mix formula. 2. Labour for traffic control, watch and ward and other miscellaneous duties at site including sundries have been included in administrative overheads of the contractor. 3. In case BM is laid over freshly laid tack coat, provision of Mechanical broom and 2 mazdoors for the same (i.e. Rs.2.97 per cum) shall be deducted as the same has been included in the cost of tack coat.			
9	Dense Graded Bituminous Macadam Providing and laying dense graded bituminous macadam using crushed aggregates of specified grading, premixed with bituminous binder @ 4.0% (min.) for Grading 1 & 4.5% (min.) for Grading 2 by weight of total mix and filler(Cement /lime / Rock dust), transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORT&H specification clause No. 505.4 complete in all respects (Reference to MORT&H's specification clause 505).			
9a	With Continuous Type HMP(60-90 TPH)			This is as per MoRT&H No. RW-24011/02/2014-Mech Dated 11.12.2015 Material cost to be added except cost of lime Consumption of materials to be followed as per - Ch. A., Sl. No.5.6 This item is to be used after getting prior approval of the concerned S.E.
(i)	for Grading 1 (37.5 mm nominal size)	cum	1127.30	
(ii)	for Grading 2 (26.5 mm nominal size)	cum	1127.30	
9b	With Continuous Type HMP (40-60 TPH)			
(i)	for Grading 1 (37.5 mm nominal size)	cum	1120.10	
(ii)	for Grading 2 (26.5 mm nominal size)	cum	1120.10	

Serial No.	Item	Unit	Rate (Rs.)	Remarks
			Labour, T&P, Machinery etc.	
1	2	3	4	5
10	Bituminous Concrete Providing and laying bituminous concrete using crushed aggregates of specified grading, premixed with bituminous binder @ 5.2% (min.) for Gr.- 1 (19mm agg size) & @ 5.4% (min.) for Gr.- 2 (13.2mm agg size), as per table 500-17, of mix and filler (Cement /lime / Rock dust), transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No.507 complete in all respects (Reference to MORT&H's specification clause 507).			This is as per MoRT&H No. RW-24011/02/2014-Mech Dated 11.12.2015 Material cost to be added except cost of lime Consumption of materials to be followed as per - Ch. A., Sl. No.5.8 This item is to be used after getting prior approval of the concerned S.E.
10a	With Continuous Type HMP (60-90 TPH)			
(i)	for Grading 1 (19 mm nominal size)	cum	1147.40	
(ii)	for Grading 2 (13.2 mm nominal size)	cum	1147.40	
10b	With Continuous Type HMP (40-60 TPH)			
(i)	for Grading I (19 mm nominal size)	cum	1135.30	
(ii)	for Grading 2 (13.2 mm nominal size)	cum	1135.30	
11	Cold Milling Cold Milling of Bituminous Pavement surface upto the required depth by mechanical means using milling machine, without disturbing the under lying layers, to proper line and level, cleaning the surface properly after milling and removing the loose materials, stacking the milled materials for re-use, necessary guarding, barricading & lighting, including hire charges of machinery, cost of fuel and labour and other incidental charges all complete and as per direction of Engineer-in-Charge.			Complete Rate
a)	For depth upto 100mm	sqm	38.50	
b)	For depth 100mm to 150mm	sqm	56.00	

D.

Under column no. 5 of Chapter 1 to 17, wherever " **Complete Rate** " appears, it means the corresponding rate under column no. 4, is inclusive of all material, labour and T&P but exclusive of Overhead Charges, Contractor's Profit and Labour Welfare Cess, unless stated otherwise.

11A, Mirza Galib Street
Kolkata-700 087
Phone & Fax : (033)2449-1523
The 17th Day of December, 2015



(Sovan Kumar Mukhopadhyay)

N.H. Planning & Design Circle
P.W (Roads) Directorate
Govt. of West Bengal